NOTES:

1.0 GENERAL

1.1 READ STRUCTURAL DRAWINGS IN CONJUNCTION WITH ALL OTHER CONTRACT DRAWINGS AND DOCUMENTS. REPORT ANY CONFLICTS TO THE ENGINEER BEFORE COMMENCING WORK.

1.2 ALL DIMENSIONS ARE APPROXIMATE AND ARE IN MILLIMETRES.

1.3 CONTRACTOR'S RESPONSIBILITY: THESE DRAWINGS DEMOLITION OF THE BRIDGE. THE REQUIRED TEMPORARY BRACING AND SHORING TO PERFORM THE WORK SAFELY IS THE RESPONSIBILITY OF THE CONTRACTOR.

1.4 ENVIRONMENTAL WORK PROCEDURES, TIMING, AND SPECIAL PRECAUTIONS SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS AND LIMITATIONS OF THE FEDERAL DEPARTMENT OF FISHERIES AND OCEANS. AND THE PROVINCIAL MINISTRY OF WATER, LAND AND AIR PROTECTION.

1.5 NO SURVEY HAS BEEN PERFORMED FOR THIS PROJECT.

2.0 DEMOLITION

2.1 ALL MATERIAL FROM EXISTING BRIDGE TO BE DISPOSED OF IN ACCORDANCE WITH ALL LOCAL, PROVINCIAL AND FEDERAL REGULATIONS.

2.2 DEMOLITION OF EXISTING STRUCTURE TO BE CARRIED OUT IN ACCORDANCE WITH CSA S350, CODE OF PRACTICE FOR SAFETY IN DEMOLITION OF STRUCTURES.

3.0 RIP RAP


3.1 ROCK SHALL BE HARD, DURABLE AND ANGULAR QUARRY ROCK OF A 4.1 SECTION 11 (FILE # 100211582) NOTIFICATION AND DFO APPROVAL QUALITY THAT WILL NOT DISINTEGRATE ON EXPOSURE TO WATER OR THE REQUIRED. ATMOSPHERE. THE GRADATION OF ROCK SIZES SHALL CONFORM TO THE FOLLOWING TABLE:

RIP RAP	ROCK GRADATION PERCENTAGE SMALLER THAN GIVEN ROCK MASS (KG)		
	15%	50%	85%
250	25	250	750

3.2 THE GRADATION OF ROCKS SHALL BE WELL-GRADED, APPROXIMAT THE SPECIFIED OR DIRECTED SIZES AND INDIVIDUAL ROCKS MINIMUM DIMENSION SHALL BE GREATER THAN ONE-THIRD ITS MAXIMUM DIMENSION AND NONE SHALL HAVE A MASS GREATER THAN FIVE TIMES THAT OF SPECIFIED RIP RAP.

3.3 THE ROCK SHALL BE MANIPULATED AS NECESSARY TO PROVIDE 1 STABILITY AND A REGULAR SURFACE WITH A MINIMUM OF VOIDS.





• © Copyright reserved. This drawing remains the exclusive property of Herold Engineering Limited and may not be reused or reproduced without written consent of Herold Engineering Limited.

20060±	
ONCRETE PIER TO BE REMOVED -305x305x4700 LONG TIMBER UPPORTS TO BE REMOVED PLAN 1:50	STEEL GIRDERS, C/W PLAN CROSS BRACING AND DIAPHRAGMS TO BE REMOVED SOUTHEAST CONCRETE ABUTMENT TO BE REMOVED FAILING TIMBER BALLAST WALL TO BE REMOVED
IMBER GUARDRAIL AND RISERS; IMBER DECK PLANKS NOT HOWN; ALL TO BE REMOVED IMBER CROSS TIE TO BE REMOVED, TYPICAL IMBER SUPPORT TO E REMOVED	FAILING TIMBER BALLAST WALL TO BE REMOVED SOUTHEAST CONCRETE ABUTMENT TO BE REMOVED
TEEL GIRDER (10x380 FLANGES AND 900 DEEP WEB) TO BE REMOVED ONCRETE PIER TO BE REMOVED	APPROXIMATE WATER LEVEL AT TIME OF SITE VISIT: APRIL 6, 2017
ROVIDE A 200 THICK LAYER OF NATIVE	APPROXIMATE GROUNDLINE AFTER REMOVAL OF ABUTMENT, FILL VOID WITH RIP AND KEY INTO EXISTING RIVER BANK EXTENT OF
XCAVATION WITH RIP RAP ELEVATION 1:50 DRAFTED JMC DRAFTING REVIEW DESIGNED SJS DESIGN REVIEW DESIGN REVIEW ATO1 Shenton Rd, Nanaimo, BC V9T 2H1 Tel: 250-751-8558 Fax: 250-751-8559 Email: mail@heroldengineering.com	DEMOLITION PLAN RIVER RECREA REGION

	4.3 EROSION AND SEDIMENT CONTROL PLAN TO BE PROVIDED AT PRE-DEMOLITION MEETING AND IN PLACE PRIOR TO DEMOLITION.
	4.4 DEMOLITION DISTURBANCE TO BE MINIMIZED NEAR OR ADJACENT TO TREED AREAS.
TELY	4.5 ENVIRONMENTAL MONITOR SHALL BE ENGAGED BY OWNER AND WILL ATTEND SITE PERIODICALLY.
ISION THE MASS	4.6 ALL TREES AND ROOTS TO BE PRESERVED WHERE POSSIBLE. ALL DISTURBED AREAS TO BE RESEEDED WITH NATIVE GRASS MIX. ANY SHRUBS OR TREES REMOVED MUST BE REPLACED AND THE AREA IS TO BE COVERED IN STRAW MULCH UPON COMPLETION.
	4.7 IN—STREAM WORK TO OCCUR DURING DRY WEATHER WITHIN FISHERIES WINDOW (JULY 15TH THROUGH SEPTEMBER 15TH).
	4.8 ALL MACHINERY TO BE CLEAN, FREE OF LEAKS, IN GOOD MECHANICAL CONDITION AND SHALL USE BIODEGRADABLE HYDRAULIC FLUIDS.
	4.9 REFUELLING OF ALL MACHINES TO BE DONE OUTSIDE OF THE 30 METER SETBACK.
	4.10 BRIDGE SITE TO BE RESTORED TO A NATURAL RIVER STATE AFTER DEMOLITION.

4.0 ENVIRONMENTAL CONSTRUCTION REQUIREMENTS

4.2 CONDITIONS OF MELP AND DFO APPROVALS TO BE FOLLOWED.

30083±

